

# **Bid Addendum Report**

## **Budhiganga Municipality, Bajura**

Budhiganga Municipality, Bajura  
Bajura  
Bajura  
Sudoor Pachism Province  
Nepal

**Addendum No: 1**

**Published On: 11-02-2022 14:00**

**Invitation No: BM/BAJURA/NCB/W/05/078-79**

**Dated On: 03-02-2022 00:00**

## Chapter: Bid Data Sheet

Sl. No.	Relevant Clause No / Name	Existing Clause	Modified Clause
1	ITB 16.1	□	□□

## Chapter: Bill of Quantities

1 Provisional Sum						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Unit Rate(in NPR)	Amount(in NPR)	
1	Insurance Provision	PS	1	25000	25000	
2	Quality Control Test	PS	1	15000	15000	
3	Project Information Board	PS	1	5000	5000	
2 Construction work						
2.1 Road Construction Work						
Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
1	Earth Work Excavation in Roadway & Using Dozer, Excavator for all types of soil and rocks	Cum	3132.17			
2	Excavation in roadway, Drain & foundation for gabion and dry wall structures including removal and satisfactory disposal & stacking or hauling (to site of embankment construction) of suitable cut materials as required and disposal unsuitable cut materials in specified manner.	Cum	150.9			
3	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per Drawing and Technical Specifications. (Locally available Material including compaction by tamping rod, without watering)	Cum	284.0			
4	Providing and laying of dry Stone Masonry Work, Stone Soling filling voids with Sand & Leveling work as per Drawing and Technical Specifications	Cum	7.2			

Procurement Item Details						
SL. No	Item Description	Unit	Quantity	Bidder's Rate(NPR)	Bidder's Rate (in words)	Total Amount(NPR)
5	Providing and laying of Plain Cement Concrete M 15 ( or 1:2:4) for nominal mix) in Foundation complete as per Drawing and Technical Specifications	Cum	3.84			
6	Providing and laying of Plum Concrete Mixing of 70% M15 Concrete and 30% boulder mixed Concrete including pipes for weep holes etc all complete as per Drawing and Technical Specifications	Cum	61.2			
7	Gabion Structure for Retaining Earth Providing and laying Gabion structure for retaining earth with diaphragm including rolling, cutting weaving , placing, laying sides and diaphragms with binding wire and filling boulders all complete as per Drawing and Technical Specification. Mesh wire- 10 Swg(0.0615 kg/m), Selvedge Wire 8 Swg ( 0.1057 kg/m), binding wire 12 Swg (0.0409 kg/m) Hexagonal mesh Type 100 mm X 120 mm	Cum	285.0			
8	Providing and laying and fixing of Geo-membrane all complete as per specification.	Sqm	210.0			
9	Making wooden form work including supply and selection of materials fixing, nailing according to drawings, placing separators, dismantling forms and hauling upto 30 m distance	Sqm	142.08			